

| No. | Items of work                                                                                                | Quantity | Per   | Rate |
|-----|--------------------------------------------------------------------------------------------------------------|----------|-------|------|
|     | <i>Aqueduct.</i>                                                                                             |          |       | Rs.  |
|     | In 4½ mile 6 vents (6½' × 3½')—                                                                              |          |       |      |
| 1   | Earthwork                                                                                                    | 174      | C.yd. |      |
| 2   | Concrete in surki mortar                                                                                     | 480      | C.ft. |      |
| 3   | Brick in surki mortar                                                                                        | 1153     | "     |      |
| 4   | Rough stone work                                                                                             | 11       | C.yd. |      |
| 5   | Burnt stone slabs 6" thick                                                                                   | 318      | S.ft. |      |
| 6   | Do 4" do                                                                                                     | 145      | "     |      |
| 7   | Plastering with mortar                                                                                       | 7·02     | Sqr.  |      |
|     | <i>Cast Bridge.</i>                                                                                          |          |       |      |
|     | In mile of 3/1 vent (3½' × 3')—                                                                              |          |       |      |
| 1   | Earthwork                                                                                                    | 53       | C.yd. |      |
| 2   | Concrete in surki mortar                                                                                     | 25       | C.ft. |      |
| 3   | Burnt brick in surki mortar                                                                                  | 768      | "     |      |
| 4   | Burnt stone slabs 6" thick                                                                                   | 96       | S.ft. |      |
| 5   | Do 4" do                                                                                                     | 84       | "     |      |
| 6   | Plastering with surki mortar                                                                                 | 1·76     | Sqr.  |      |
| 7   | Gravelling road way                                                                                          | 2        | C.yd. |      |
|     | <i>Raising Dasappankatte Tank bund in ½ mile.</i>                                                            |          |       |      |
| 1   | Earthwork                                                                                                    | 559      | C.yd. |      |
| 2   | Turfing                                                                                                      | 460      | S.yd. |      |
|     | <i>Dasappankatte Waste Weir.</i>                                                                             |          |       |      |
| 1   | Earthwork                                                                                                    | 27       | C.yd. |      |
| 2   | Concrete in surki mortar                                                                                     | 90       | C.ft. |      |
| 3   | Brick in surki mortar                                                                                        | 819      | "     |      |
| 4   | Rough stone work                                                                                             | 24       | C.yd. |      |
| 5   | Burnt stone slabs 6" thick                                                                                   | 118      | S.ft. |      |
| 6   | Plastering with surki mortar                                                                                 | 1·76     | Sqr.  |      |
|     | Deviation of Nalla from Kethanahalli into Nalla from Amragere above the aqueduct in 4½ mile on left channel. |          |       |      |
| 1   | Earthwork excavating channel and cross binding nalla.                                                        | 977      | C.yd. |      |

R. W. SCALDWELL,  
Executive Engineer

#### SHIMOGA DIVISION.

Notice dated 3rd October 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 25th October 1928, for restoring Kunetappa Doddakere Tank, Registered No. 121 of Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

| Description of work | Unit of work | Rate per unit |
|---------------------|--------------|---------------|
|                     |              |               |

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kunetappa Doddakere Tank, Registered No. 121 of Sorab Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer of Shimoga Division who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Revised abstract estimate of quantities for restoring Kunetappa Doddakere Tand, Registered No. 121, Sorab Taluk, Shimoga District.

| No.                                                                                                                  | Items of work                                                                                           | Per      | Quantity |
|----------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|----------|----------|
| <i>Bund at R.L. 55'00</i>                                                                                            |                                                                                                         |          |          |
| 1                                                                                                                    | Clearing thorny bushes, scraping grass and cutting grips to receive new earth.                          | Lump sum | Rs.      |
| 2                                                                                                                    | Earthwork to bund including watering and tamping, complete...                                           | Cyd.     | 10,623   |
| 3                                                                                                                    | Turfing to front and rear slopes of bund ...                                                            | Sqr.     | 855'89   |
| 4                                                                                                                    | Providing and fixing grade stones including bed slabs chiseling figures and painting, complete.         | Each     | 16       |
| 5                                                                                                                    | Do Index stones ...                                                                                     | "        | 16       |
| 6                                                                                                                    | Providing and fixing date stone including chiseling figures and painting.                               | "        | 1        |
| 7                                                                                                                    | Do Registered No. stone ...                                                                             | "        | 1        |
| 8                                                                                                                    | Providing and fixing gauge stone 12' high including chiseling figures and gauge and painting, complete. | "        | 1        |
| 9                                                                                                                    | Do B M stones, complete ...                                                                             | "        | 2        |
| <i>Dismantling the damaged masonry sluice at right and constructing a new C.I.P. sluice with cill at R.L. 44'50.</i> |                                                                                                         |          |          |
| 1                                                                                                                    | Earthwork cutting and opening the bund ...                                                              | C.yds.   | 81       |
| 2                                                                                                                    | Do refilling with consolidation ...                                                                     | "        | 90       |
| 3                                                                                                                    | Do excavation for foundation ...                                                                        | "        | 8        |
| 4                                                                                                                    | Metal concrete with surki mortar ...                                                                    | C.ft.    | 195      |
| 5                                                                                                                    | Burnt brick in surki mortar ...                                                                         | "        | 237      |
| 5 (a)                                                                                                                | or burnt stone in surki mortar ...                                                                      | "        | 237      |
| 6                                                                                                                    | Burnt stone slabs 6" to 4½" thick ...                                                                   | S.ft.    | 71       |
| 7                                                                                                                    | Surki plastering ...                                                                                    | Sqr.     | 3'53     |
| 8                                                                                                                    | Providing teakwood plug with iron rod and locking arrangements, complete.                               | Lump sum | Rs.      |
| 9                                                                                                                    | Dismantling old masonry ...                                                                             | "        | "        |
| 10                                                                                                                   | Cutting holes in orifice and gibbet slabs ...                                                           | "        | "        |
| 11                                                                                                                   | Providing cast iron pipes of 9" dia. including cost, freight and fixing in cement, complete.            | R.ft.    | 24       |

| No.                                                                                             | Items of work                                                                      | Per   | Quantity |
|-------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------|-------|----------|
| <i>Waste Weir, Right at R. L. 50'00.</i>                                                        |                                                                                    |       |          |
| 1                                                                                               | Earthwork excavation for body wall and returns                                     | Cyd.  | 16       |
| 2                                                                                               | Metal concrete in surki mortar                                                     | C.ft. | 42       |
| 3                                                                                               | Burnt bricks in surki mortar                                                       | "     | 86       |
| 3(a)                                                                                            | or Burnt stone in surki mortar                                                     | "     | 86       |
| 4                                                                                               | Burnt stone slabs dressed and fixed 1½" to 6" thick                                | S.ft. | 23       |
| 5                                                                                               | Surki plastering                                                                   | Sqr.  | 155      |
| 6                                                                                               | Clearing draft and approaches                                                      | L. S. | Rs.      |
| 7                                                                                               | Dismantling the existing returns at left end for extension and other sundry works. | "     | "        |
| <i>Waste Weir, Left at R. L. 50'00 with a Sluice Vent in it having its sill at R. L. 48'00.</i> |                                                                                    |       |          |
| 1                                                                                               | Draft clearing and using earth to bund                                             | L. S. | "        |
| 2                                                                                               | Earthwork excavation for foundation                                                | Cyd.  | 1        |
| 3                                                                                               | Metal concrete in surki mortar                                                     | C.ft. | 12       |
| 4                                                                                               | Burnt brick in surki mortar                                                        | "     | 16       |
| 4(a)                                                                                            | or burnt stone in surki mortar                                                     | "     | 16       |
| 5                                                                                               | Burnt stone slabs dressed and fixed 4½" X 6" thick                                 | S.ft. | 14       |
| 6                                                                                               | Providing teakwood plug and iron rod with locking arrangement complete.            | L. S. | "        |
| 7                                                                                               | Cutting holes in orifice slabs, etc.                                               | "     | "        |
| 8                                                                                               | Providing earthen ware pipe of 6" dia. and fixing in cement complete.              | R.ft. | 6        |
| 9                                                                                               | Excavating off take channel                                                        | L. S. | Rs       |
| 10                                                                                              | Repairing body wall then and there, dismantling at sluice vent, etc.               | "     | "        |
| 11                                                                                              | Surki plastering                                                                   | Sqr.  | 1'00     |

M. A. SRINIVASACHARI.  
Executive Engineer.

## KADUR DISTRICT.

Notice dated 4th October 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur up to 30th October 1928, till 2 P.M., for "constructing Police Station at Ajjampur, Tarikere Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

| Description of work | Unit of work | Rate per unit |
|---------------------|--------------|---------------|
|                     |              |               |

4. Each tender must be accompanied by a deposit of Rs. 70 (seventy only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Station at Ajjampur", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.